

SS-600



Solar Panel: 2 × 455W, Mono

GEL Battery: 4 × 150Ah, DC12V

Lamp: 4 × 60W LED, IP65, 36000Lms

Tilt: 90° Electric

Controller: 60A MPPT, 95% Efficiency

Mast: Steel Q235, Square Telescopic type, 6m/7m/9m

Manual Winch/Electric Winch, Lifting, 70kg

Load, 100kph Windproof

**Trailer: US Standard, Ball Hitch, Single Axle, Manual
Outrigger**

Charging Time: 8.8 hours

Running Time: 19.2 hours

